

Reduce Risk in the Field: A Key to Success in Mechanical Contracting

Chad Salge, Vice President of Virtual Design and Engineering – The Brandt Companies
Rick Dustin, Vice President, Engineering Solutions Group – McKenney's

May 2025

WAVES of **INNOVATION**
TOGETHER WE RISE





Special Thanks to our Sponsors:



Waves of Innovation



Chad Salge - Vice President
Virtual Design and Engineering



Rick Dustin - Vice President
Engineering Solutions Group





What are YOUR risks and how do YOU mitigate them?



slido

- Scan QR code on left with your smartphone or tablet.
- You will be prompted to answer a question at a time.
- Q&A will also be available within the Slido throughout this session.
- We will address questions at end of presentation.

Agenda

- I. Problem Statement and Session Goals
- II. Understanding Contract Documents
- III. BIM Coordination / Fabrication
- IV. Field Productivity & Planning
- V. Multi-trade Assemblies
- VI. Field Training
- VII. Questions



Problem Statement



- As contractors, **our biggest risk is labor in the field.**
- Scopes are getting larger and schedules are getting more and more compressed.
- Clients are expecting us to do more with less time on site.
- **How do we reduce our risk to ensure our success?**



Goals for This Session



- Walk away with tangible takeaways to address and control your risks on upcoming projects.
- Understand how fellow contractors are approaching these risks.
- Meet a few peers that can share what they are doing to address this opportunity.






Understanding Contract Documents (Project Specific Drawings and Specifications)

Contract Documents




- *Contract Documents:*
 - *Define the cardinal scope of the project*
 - *Comprised of drawings and specifications.*
- *Typical Workflow:*
 - *Contract drawings converted into shop drawings by an installing contractor*
 - *Shop Drawings reviewed by the Engineer of Record.*



Contract Documents



- *People are drawn to contract drawings to understand scope since they are diagrammatic in nature.*
- *Contract specifications tend to get neglected since the traditional form of delivery is a 1000-page book.*




Specifications



- *A written document describing in detail the scope of work, materials to be used, methods of installation, and quality of workmanship for a parcel of work to be placed under contract; usually utilized in conjunction with working (contract) drawings in building construction.*

** Dictionary of Architecture and Construction

- **FOUNDATION FOR SUCCESS OR FAILURE**



Specifications of Today

- Fill Gaps in Design
- Shifts Liability



A. General:

1. Industry Practices: Install pipe, tube, and fittings in accordance with recognized industry practices which will achieve permanently leak-proof piping systems, capable of performing each indicated service without failure or degradation of service. Install each run with a minimum of joints and couplings, but with adequate and accessible unions or flanged

3. Expansion and Contraction: Install loops, offsets, sizing joints, and expansion joints, as necessary, to avoid strain resulting from expansion and contraction of piping systems on fixtures and equipment. Provide three (3) Victaulic grooved connections required by the application to

hangers. Provide fittings at changes in direction. Piping in finished areas shall be concealed, except in mechanical rooms. Where pipes of different sizes join, provide reducing elbows, tees, or couplings. Bushings will not be acceptable.


3. Expansion and Contraction: Install loops, offsets, sizing joints, and expansion joints, as necessary, to avoid strain resulting from expansion and contraction of piping systems on fixtures and equipment. Provide three (3) Victaulic grooved connections required by the application to



Specifications of Today



Platform for
“Trading” Costs.



Specifications of Today



Matrix Format (Material Standard)

- Place on contract drawings to condense spec book
- Provide expedited understanding of materials and methods of installation.

SAMPLE JOB		VERSION 1.0															REV0										
PVF MATERIAL STANDARDS																											
SYSTEM	U/G (BURIED)	A/G (HANGING)	QUALIFIER	ID	SIZE (INCH)		PIPE	FITTINGS	JOINT	INSULATION THICKNESS (SEE NOTE 0)	LETTERED NOTES (SEE KEY)										Numbered Notes (See Key)						
					MIN	MAX					DOMESTIC	BRANCHES			WELDS/MTR												
										NOT REQ'D	PIPE	FITTINGS	ORIGIN	FITTINGS	O-LETS	SADDLES	PULLED TEE	PEX	ASME B31.9	ASME B31.3	ASME B31.1	SHOP WELD	FIELD WELD	INSPECT	MTR REQ'D		
SANITARY DRAIN U/G STORM DRAIN U/G	X		DWV System	PVC/DWV	1-1/4	16	PVC PIPE SCH40 (CHARLOTTE)	PVC SCH40 SOLVENT WELD (CHARLOTTE)	PVC SCH40 SOLVENT WELD COUPLING #100 DWV (CHARLOTTE)	NONE	X				X												10
CHILLED WATER CONDENSER WATER HEATING HOT WATER				(CUMR) 2			1/4 2 2-1/2 20 24 48 CS PIPE TYPE L HARD STD PE (GENERIC) CS PIPE ASS ERW STD BLK BE (GENERIC) CS PIPE API-5L SAWL STD BLK BE (GENERIC)	COOPER WHOT SOLDERED (MBCO) CS STD WEIGHT BUTT WELD (GENERIC)	SOLDERED 90S DS CxC COUPLING (MBCO) BUTT WELD (GENERIC)	CW 1-1/2" INS. ALL PIPES (E2,E1) PPE: 6 1-1/2" PIPE + 1-1/2" INS. (E2) 6 1-1/2" PIPE + 2" INS. (E2,E1)	X																
NATURAL GAS				(MGRP X SW) 2			1/2 2 2-1/2 10 CS PIPE ASS ERW STD BLK BE (GENERIC)	MEGAPRESS FITTINGS (VEGA) CS STD WEIGHT BUTT WELD (GENERIC)	MEGAPRESS PXP COUPLING (VEGA) BUTT WELD (GENERIC)	NONE	X		X														1, 12, 17 1, 12
SANITARY WASTE & VENT STORM & OVERFLOW DRN REAR WASTE & VENT				(NH) STD			2 4 5 10 12 10 NH PIPE (TYLER) NH PIPE (TYLER)	NH FITTINGS (TYLER)	NH COUPL. 2 SAND (TYLER) NH COUPL. 4 SAND (TYLER) NH COUPL. 6 SAND (TYLER)	HORIZONTAL STORM DRAIN ONLY GETS 1" INS. (D3)	X		X														7, 18, 20

Submittal Approval



Does an Approved Submittal alleviate Responsibility from Us?

- The verbiage in the submittal stamp has contractual implications.

- | | |
|---|--|
| <input type="checkbox"/> No Exception Taken | <input type="checkbox"/> Rejected |
| <input type="checkbox"/> Revise and Resubmit | <input type="checkbox"/> Submitted Specified Item |
| <input type="checkbox"/> Make Corrections Noted | <input checked="" type="checkbox"/> Submittal Receipt Acknowledged |

Checking is only for general conformance with the design concept of the project and general compliance with the information given in the contract documents. Any action shown is subject of the requirements of the plans and specification. Contractor is responsible for dimensions which shall be confirmed and correlated at the job site; fabricated process and techniques of construction; coordination of his work with that of all other trades and the satisfactory performance of his work.

<input checked="" type="checkbox"/>	Approved	Fabrication/installation may be undertaken. Approval does not authorize changes to the Contract Sum or Contract Time.
<input type="checkbox"/>	Approved as noted	
<input type="checkbox"/>	Revise and resubmit	Fabrication and/or installation MAY NOT be undertaken.
<input type="checkbox"/>	Rejected	
Contract conditions place the responsibility for dimensions, coordination and compliance with Contract Documents on the Contractor.		
By: RCG	Date: 03/31/2017	



BIM Coordination / Fabrication

Workflows



Workflows




- Utilizing "planning workflows" like BIM Coordination and Fabrication allow you to minimize risk at an early stage in the project lifecycle.
- If you have in-house design and BIM resources, it will allow you to model with a constructability mindset from the onset of design.
- This level of planning makes for robust scope development and a lesser chance for "gotchas" (risk) in the field.




Manage the Model in the Cloud



Bi-Directional





Shop Fabrication and Site Install




Models and Docs Shared Thru 360

Docs



Design Rendering: Complete Penthouse Piping



Spool View in Stratus



Dashboard Viewer

Project Test Project Model Level U2 Basement Piping Assembly U2-CHWR-CHILLER_1 Spool

Show hidden parts shaded

Parts Sheet Report Attachments

Generate PDF 1 / 1 Zoom Out Zoom In 50%

96705432
 Test Project
 3/28/2016 9:51 AM
 Level U2 Basement Piping
 Chiller CHWR
 U2-CHWR-CHILLER_1
 Slip Status

McKenney's

Quantity	ID	Diameter	Material	Cut Length	Manufacturer	End 1	End 2	Weight	Pi
1	3	6	Carbon Steel	0.00		0E	0E	0.00	
1	5	6	ACS	12.74		0E	0E	16.97	
1	1	8	ACS	20.00		0E	0E	28.00	
1	7	8	ACS	97.21		0E	0E	28.00	

Cooling Tower Rack



Pump Skid



Pipe Rack




Production Model

Real-Time Updates!



Display Modes			
	Coordinated	0	0.0 %
	Issued for Fabrication	167	25.0 %
	Issued for Purchasing	0	0.0 %
	Purchased	0	0.0 %
	Materials Received	0	0.0 %
	Cutting	0	0.0 %
	Pipe Prep	0	0.0 %
	Welding	192	28.8 %
	Assembly	226	33.9 %
	Loading	82	12.3 %
	Complete	0	0.0 %





Productivity and Planning

Stratus Progress Dashboard



Packages
+ New Package
Import CSV
Refresh
Status Active
Report
Progress Tracking Dashboard

Show 10 Entries CSV Excel

Drawing	Package Name	Cost Code	Pieces	Weight	Length	1.0 Installation Hours	Hanging Factor	Adjusted Installation Hours	Material Cost	Status	Last Status Change	Parts Installed	Parts Ready to Install
Project Warehouse-PLB-R21	Package - SUPPORT		10	181	5'-5"	8	0.90	7	\$368	Installed	5/24/2022	10	0
Project Warehouse-PLB-R21	Package - SWV		208	3724	374'-7"	191	0.90	172	\$6520	Spoiled	5/24/2022	173	28
Project Warehouse-PLB-R21	Package - WASTE		80	1589	277'-3"	108	0.90	97	\$0	Installed	5/24/2022	80	0
Project Warehouse-PLB-R21	Package - TRAP PRIMERS		46	88	100'-3"	15	0.90	13	\$258	Installed	5/24/2022	46	0



Hanger Factor Editable by Package/Cost Code



Package Status Progress

Installation Tracker




Project Comparison – Sheet Metal



Ductwork Installation Comparison

		Estimated P..	Actual Prod..	Quantity	Installed Qu..	Pieces	Installed Pi..
Sheet Metal	14511587 - Norfolk Fusion Tenant	18.0	16.8	133,915	112,197	32,744	0
Field	15006019 - 1105 West Peachtree Office Park..	22.0	23.3	256,956	228,731	19,118	0
	15006026 - 8 West	27.1	45.9	58,706	58,706	2,906	2,906
	15006027 - 712 West Peachtree	33.0	28.1	160,668	160,668	5,338	5,338
	15006028 - 1105 West Peachtree Hotel	17.8	16.7	15,490	15,490	2,176	2,176
	15006030 - Fusion	28.7	25.3	215,221	215,221	13,130	13,130
	15006031 - Kimball Bridge Office and Parkin..	38.4	28.0	79,715	65,611	2,032	0
	15006032 - Midtown Union	42.9	62.7	246,325	197,288	8,670	0
	16001074 - Three Ballpark Center	16.3	19.8	53,177	53,177	3,214	3,214
	16001090 - Emory Rollins School of Public H..	25.9	17.0	99,015	65,436	5,852	0
	19001578 - Emory Musculoskeletal MOB	25.1	27.8	246,208	203,887	20,898	0
	19001581 - Grady Ponce De Leon Center	10.5	10.3	23,020	18,400	4,396	0
	72500246 - Charlotte Metro	24.0	21.1	269,298	159,697	13,227	0
Grand Total		25.6	25.2	1,857,715	1,554,511	133,701	0


Project Comparison – Sheet Metal





Mult-trade Assemblies/Racks

Utility Corridor Rack



Utility Corridor Rack



Healthcare Patient Tower Corridor



First-of-Kind (FOK) Inspections



What Are They?

Complex or Repetitive Work

Why Perform Them?

Verify Compliance to Documents

Refine Installation Methods

Identify/Correct Quality Concerns

First-of-Kind (FOK) Inspections



Focus of the Inspections:

- *Goal:* to build all 56 identical skids offsite and perform crane lift to set them in place using less time
- Confirm design compliance and dimensional layout and arrangement for connection to thermal storage and chillers
- Establish conformity for repeatable production
- Serviceability of control valves, control devices and strainers
- Maintaining clearance for pipe and equipment insulation
- Verify rigging points for safe handling in the shop, loading and delivery, and onsite for crane lift
- Verify final connections to tanks and chillers

First-of-Kind (FOK) Inspections



1. Verify T&B can access PT ports, some are turned in toward adjacent pipe
2. Verify gripple cable can pull through and is not restricted where unigrip does not line up with a strut hole
3. Ensure Inglett and rigging teams are handling racks in a way to prevent damage to the drain the extends beyond the bottom strut.
4. Longitudinal 13/16" strut is causing a pipe stub up to be off center and will not allow for full insulation. Strut may need to be removed in this section after setting on floor. Additionally this strut was added after modeling so confirm it does not generate any unforeseen clashes.





Reality Capture

Reality Capture – LIDAR Scanning




Image above is a point cloud file that can be incorporated into your modeling software.

- Scanning technologies facilitate a planning workflow that allows you to identify existing obstacles, tie-in points, etc. So that you can BIM and fabricate with a higher level of accuracy.
- This technology can be incorporated in Existing Building renovation projects and Greenfield projects.

Reality Capture – Photogrammetry



- Photogrammetry is technology used to create virtual walkthroughs by stitching millions of photos from a scanner together.
- This technology can be used to get a sense for the risks that you will encounter on a job site.

Image above is a floor plan created from scanning an existing facility with a Matterport scanner.

Reality Capture – 360 Camera




Image above is a timeline comparison of two capture dates on site as construction was progressing.

- 360 degree cameras are utilized to produce 3D walkthroughs of spaces.
- This technology can be used to track construction progress and tie milestones in schedule to actual progress. BIM can be tied to this technology to track linear feet of install and understand productivity in the field.
- This is also an effective way to track damages on a project.



Field Training

Targeted Field Training – Sheet Metal Excellence



TDF Station

- Sealing of Duct
- Gasketing
- Corner bolts/screws
- TFD Clip Installation



Damper Installations

- Required Framing
- Installation in Wall
- Attachments / Angles



250+ Team Members Trained

Round Taps

- Cutting of Openings
- Attachments
- Proper Sealing

Targeted Field Leadership Training



- Level Up training conducted by regional training resources for over 400 employees. Focus was on leadership skills in the field in order to enhance influence by supervision and reduce incidents and altercations.
- Training consisted of the following elements:
 - Emotional Intelligence
 - Building Relationships
 - Effective Communication
 - Managing Conflict
 - Situational Leadership
 - Decision Making and Problem Solving
 - Safety and Risk Management





Questions



Breakout Workshops



Thank you!

If you would like to receive PDH credit for this session, please be sure to provide your feedback in the applicable session survey. (Also available via the event App!)

**Surveys close 6/4/25*